

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN RECEIVED

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 RECONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 22 PM 1:29

*Jean Stace*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on DEC. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-8 cor. common to Sec. 19 & 20, T27N-R7W
- 1850 GLO re-survey: set post, Beech 14", N16W 5, Hemlock 9", S86E, 18. 10-19-08, W.S. Merrill, Co. Surv., fd original gov't. bearing trees and cedar stake.
- 5-1952, A.L. Drago, Co. Surv., fd old stake and stp of 1 gov't bearing tree.
- 9-5-73, J.L. Wilcox, fd 3/4" pipe, Liber 1, Pg 424 of Surv.
- 3-7-73, LCRC Liber 1 Pg 192.
- 9-11-73, LCRC Liber 1 Pg 267.
- 1-6-76, J.L. Fletcher, used cor., Liber 1 Pg 822 of Surv.
- 11-21-77, J.L. Fletcher, fd 7/8" iron pipe, Liber 2 Pg 137 of Surv.
- 12-6-77, J.L. Fletcher, fd 3/4" iron pipe, Liber 2 Pg 147 of Surv.
- 8-18-78, J.L. Fletcher, fd, Liber 2 Pg 245 of Surv.
- 6-26-79, J.L. Fletcher, fd, Liber 2 Pg 362 of Surv.
- 7-9-93, E. Farrier, fd 1/2" iron pipe, Liber 4 Pg 170 of Surv.
- 7-12-93, E. Farrier, fd 1/2" iron pipe, Liber 4 Pg 171 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 cor. common to Sec. 19 & 20, T27N-R7W  
Found and accepted 1"x24" Iron Pipe 5' East and 10' South of trail road. 75'+/- South of edge of swamp.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 cor. common to Sec. 19 & 20, T27N-R7W  
Found 1"x24" Iron Pipe - Pulled pipe and set 5/8"x36" re-rod w/ Aluminium Cap.  
N20E, 61.06', 12" W. Oak, reset.  
N75E, 56.13', 14" W. Pine, reset.  
N22W, 32.83', 20" W. Oak, set.  
S44W, 81.83', 10" W. Oak, set.

Signed by Eugene Farrier Date 12-22-93

Surveyor's Michigan License No. 24594