

**SURVEY &
REMONUMENTATION**

FEB 18 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 REMONUMENTATION	T <u>27N</u> R <u>7W</u>	<u>C-9</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:29

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on DEC. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

C-9 cor. common to Sec. 19, 20, 29 & 30, T27N-R7W
1850 GLO re-survey: fd post, Beech 16", S23W 46, Hemlock 14", N33E, 22.
4-1-69, M.A. Koivisto, MDOT, set 1 1/2" iron pipe from U.S. 131 plans.
9-5-73, J.L. Wilcox, fd 1 1/2" pipe, Liber 1, Pg 424 of Surv.
9-11-73, LCRC Liber 1 Pg 263.
1-6-76, J.L. Fletcher, used cor., Liber 1 Pg 822 of Surv.
11-21-77, J.L. Fletcher, fd 1 1/2" iron pipe, Liber 2 Pg 137 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 cor. common to Sec. 19, 20, 29 & 30, T27N-R7W
Found and accepted 1 1/2" Iron Pipe w/ accessories, 1.3' hi in low wet area. Could not determine GLO ref. stumps, under water.
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 cor. common to Sec. 19, 20, 29 & 30, T27N-R7W
Found 1 1/2" Iron Pipe, 1.3' hi in low wet area. Set 5/8"x36" re-rod w/ Aluminium Cap inside pipe.
S12E, 73.96', 10" J. Pine, fd nail & MDSH tag.
S29W, 43.98', 12" J. Pine, fd nail & MDSH tag.
S64W, 49.79', 16" R. Pine, fd nail & MDSH tag.
North, 24.38', Tw. 10" Cottonwood.

Signed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-93