

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)		Located In:	Corner Code: #
1993 REMONUMENTATION			
1. Public Land Survey	T 27N R 7W	C-11	
	T R		
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:29

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on NOV. 23, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
C-11 cor. common to Sec. 29, 30, 31 & 32, T27N-R7W
1850 GLO re-survey: set post; Beech 8", S21E, 20; Sugar 18", N45W, 31.
12-31-1888, E. Mosher, Co. Surveyor, no accessories.
1905, W.S. Merrill, Co. Surveyor, fd old stake, set iron stake (T rail).
1907, W.S. Merrill, Co. Surveyor, visited cor. no accessories.
1925, W.S. Merrill, Co. Surveyor, T rail, no accessories.
MDOT, Surv of U.S. 131, visited cor.
12-27-71, J.F. Erickson, fd R.R. Iron, Liber 1 Pg 50 of Surv.
8-14-71, LCRC Liber 1 Pg 42.
12-71, N.F. Parker, fd R.R. Iron, survey, Northern Mich. Gas.
6-15-72, N.F. Parker, fd R.R. Iron, Liber 1 Pg 251 of Surv.
9-12-72, LCRC Liber 1 Pg 154.
7-13-73, LCRC Liber 1 Pg 241.
5-21-75, J.L. Wilcox, fd R.R. Rail, Liber 1 Pg 957 of Surv.
2-22-78, J.L. Wilcox, visited cor., Liber 2 Pg 296 of Surv.
11-24-80, J.I. Nelson, fd R.R. Rail, Liber 2 Pg 616-618 of Surv.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-11 cor. common to Sec. 29, 30, 31 & 32, T27N-R7W
Found and accepted R.R. Rail 1" below surface @ C/L intersections of Motz and Prough road. Believe GLO & Co. Surv. witnesses destroyed from pipeline to North & other clearing.
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful perpetuation of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:
C-11 cor. common to Sec. 29, 30, 31 & 32, T27N-R7W
Found R.R. Rail 1' E. of N. fence line, set 5/8"x18" re-rod w/Brass Cap over rail, set 0.7' below surface.
N60W, 70.62', 18" Maple, fd N/tag.
N46E, 51.73', P. Pole.
N2E, 50.10', 1/2 re-rod.
North, 33.19', fence post.



Signed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-93