

**SURVEY & REMONUMENTATION**

MAR 21 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN RECEIVED

97 JAN 31 PM 3:21

For corners in

KALKASKA

(County)

Located In:

Corner Code ##

1996 REMONUMENTATION

- |                                    |                          |       |
|------------------------------------|--------------------------|-------|
| 1. Public Land Survey              | T <u>27N</u> R <u>7W</u> | C-12  |
|                                    | T _____ R _____          | _____ |
|                                    | T _____ R _____          | _____ |
|                                    | T _____ R _____          | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____ |
|                                    | S _____ T _____ R _____  | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____ |
|                                    | S _____ T _____ R _____  | _____ |

*Joan Hall*  
REG. DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on July 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- C-12: Cor. common to Sec. 31 & 32, T27N-R7W, Kalkaska Township  
1850, GLO resurvey, set post. 10" Beech N51W 10, 6" Hemlock S75E 35.  
May 16, 1907, W.S. Merrill, Co. Surveyor, set cor., 24" Pine N81W 25.  
Jun 24, 1912, W.S. Merrill, Co. Surveyor, used cor., no accessories.  
Aug 14, 1971, LCRC Liber 1 Pg. 41.  
Dec 23, 1971, J.F.Erickson, fd 3/4" iron bar. Liber 1 pg. 50 of Survey.  
Jun 15, 1972, LCRC Liber 1 pg. 154.  
Jun 15, 1972, N.F.Parker, fd 5/8" bar. Liber 1 pg. 251 of Survey.  
Jun 06, 1973, LCRC Liber 1 pg. 241.  
05-28-1974, J.L.Wilcox, fd 1" iron bar. Liber 1 pg. 619 of Survey.  
02-22-1978, J.L.Wilcox, used corner. Liber 2 pg. 296 of Survey.  
06-01-1979, J.L.Fletcher, fd. 1" iron bar w/ accessories.  
11-24-1980, J.I.Nelson, fd 1" iron bar. Liber 2 pg. 614, 616, & 618 of Surveys.  
08-31-1982, E.D.Farrier, Survey #4782, fd. 1" iron bar w/accessories.  
10-30-1995, E.D.Farrier, Survey #22095, fd. 1/2" iron & cap w/ accessories.

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-12: Cor. common to Sec. 31 & 32, T27N-R7W, Kalkaska Township  
Found 1/2" iron & cap and old axle shaft w/ 5/8" round head. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 0.5' below Motz rd. surface, cor falls 4' West of centerline of Motz rd. & 25' North of existing Shell Pipeline. No G.L.O. witnesses were found. The Kalkaska Co. peer group approved & accepted the above monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-12: Cor. common to Sec. 31 & 32, T27N-R7W, Kalkaska Township  
Found 1/2" iron & cap and old axle shaft w/ 5/8" round head. Pulled & Set 5/8" x 18" re-rod w/ Brass cap 0.5' below Motz rd. surface, cor falls 4' West of centerline of Motz rd. & 25' North of existing Shell Pipeline.  
Set nail & tag N50W, 12" Poplar, 24.87'  
East Face of 3" Steel Post, 33.49'  
Set nail & tag S64W, Consumer Power Pipeline Anode (Woodpost) 58.74'  
West Conc. Mon. 32.92'

Signed by *Eugene Farrier* Date 1-30-97  
Surveyor's Michigan License No. 24594

