

SURVEY &
REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code <u>≠#</u>
1993 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:30

Joan Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on DEC. 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9 cor. common to Sec. 20 & 29, T27N-R7W
1850 GLO re-survey: Set fir post Birch 10", N29W, 08; Beech 10", S1W, 30.
1888, E. Mosher, Co. Surv., Hem 30" S22W, 47, Hem 18" N9E 67 or 63.
1905/1925, W.S. Merrill, Co. Surv., S. Maple 7", N5E, 54, S. Maple 7", N26W, 42.
5-1952, A.L. Dragoo, Co. Surv., fd old stake, no accessories.
4-1-69, M.A. Koivisto, MDOT, fd cedar post knocked down, set 3/4" pipe
26" Maple, N45E, 85.30', 21" Maple, N20W, 28.18', 20" Poplar, West, 62.80'
11-21-77, J.L. Fletcher, fd 3/4" iron pipe, Liber 2 Pg 52
1-18-82, LCRC Liber 2 Pg 254.
12-12-90, T.E. Brand, Re-established by witness setting 1/2" re-rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 cor. common to Sec. 20 & 29, T27N-R7W
Found and accepted 1/2"x18" re-rod w/ #24594 cap, 3' E. of N-S fence, fd 2 nails in trees of record
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 cor. common to Sec. 20 & 29, T27N-R7W
Found 1/2"x18" re-rod w/ #24594 cap, replaced w/ 5/8" re-rod with 3 1/4 Aluminum Cap 0.5' below surface.
N75W, 3.04', fence post, fd nail S. fc.
S23E, 90.99', 14" R. Pine, fd nail W. fc.
N8W, 28.28', 22" Tw. Maple, fd nail W. fc.
S23W, 46.76', 8" Tw. Cherry, set.
N55E, 48.63', 6" W. Pine, set.
N87W, 62.84', 20" Poplar, fd spk w/tag



Signed by *Eugene FARRIER*
Surveyor's Michigan License No. 24594

Date 12-22-93