

**SURVEY &
REMONUMENTATION**

KALKASKA COUNTY, MICHIGAN
RECEIVED

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC 27 AM 9:53

For corners in

COMMISSION

KALKASKA
(County)

Located In:

Corner Code #/

1995 REMONUMENTATION

1. Public Land Survey	T <u>27N</u> R <u>7W</u>	E-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Joan Hall
REG. DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on NOV. 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-12: Cor. common to Sec. 32 & 33, T27N-R7W, Kalkaska 1850 GLO re-survey: set 1/4 Sec. post, Sgr 20", S13E, 29; Sgr 10", N10W, 42. 1901, W.S. Merrill, Co. Surv, used crnr, no accessories.
- 12-28-1978, LCRC (J.L. Fletcher), E-12, Set 1/2" iron rod, L.2 PG.165.
- 11-24-1980, J.I. Nelson, CERT OF SURV, fd. 1/2" iron/cap #19830, L.2 PG.614.
- 10-26-1984, E.D. Farrier, CERT OF SURV, used iron w/cap #19830.
- 4-19-1993, E.D. Farrier, CERT OF SURV, fd. iron w/cap #19830, L.2 PG.616.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12: Cor. common to Sec. 32 & 33, T27N-R7W, Kalkaska Fd 1/2" iron w/cap #19830, 2' East of c/l M-66. Pulled & replaced with 5/8" x 18" R.B. w/brass cap in Mon.box. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.


Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-12: Cor. common to Sec. 32 & 33, T27N-R7W, Kalkaska Fd 1/2" iron w/cap #19830. Pulled & replace with 5/8" x 18" R.B. w/brass cap in Mon.box.
- Set nail & tag S50W, fd. iron w/cap "Mitchell", 46.54'
- Set nail & tag South, fd. pknail E. c/l M-66, 33.00'
- Set nail & tag East, 14" Spruce, 50.97'
- Set nail & tag S60W, 6" R. Pine, 56.35'

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-95



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
REVISED JAN. 197