

**SURVEY &
REMONUMENTATION**

JAN 17 1996

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

KALKASKA COUNTY, MICHIGAN
RECEIVED

95 DEC 27 AM 9:53

For corners in **COMMISSION**

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code #:
1995 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Jan Stille
REG. OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, EUGENE FARRIER, in a field survey on Nov. 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13: Cor. common to Sec. 32 & 33, T27N-R7W, Kalkaska
1850 GLO re-survey: set cor. post, Sgr 12", N55W, 24; Sgr 14", N42E, 70.
1937, MDOT, fd. 3"x3"wd.stk&stns, w/accessories, Set 1 1/2" axle shaft.
11-5-1975, LCRC(H.L.Fluhart), E-13, fd 3/8"rerod in Mon.box, L.1 PG.365-A.
12-28-1978, LCRC(J.L.Fletcher), E-13, fd 3/8"rerod in Mon.box, L.2 PG.165.
11-24-1980, J.I.Nelson, CERT OF SURV, fd 3/8"rerod in Mon.box, L.2 PG.616.
5-25-1993, E.D.Farrier, CERT OF SURV, fd iron, L.4 PG.161.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13: Cor. common to Sec. 32 & 33, T27N-R7W, Kalkaska
Fd 1/2" R.B. in Mon.box, 10.2' East of c/l M-66 & in c/l Anderson Rd.
Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface.
No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument and is accepted as the best available evidence of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County

Chairman Eugene Farrier

Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13: Cor. common to Sec. 32 & 33, T27N-R7W, Kalkaska
Fd 1/2" R.B. in Mon.box. Pulled & replace with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface.
Set nail & tag S25E, 8" R. Pine, 110.00'
Set nail & tag S40E, 12" R. Pine, 106.43'
Set nail & tag S55E, 12" R. Pine, 109.47'
West, Cor. common to Sec. 4 & 5, T26N-R7W, Kal.Co.Mon., 54.96'

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-95

