

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA

(County)

1993 REMONUMENTATION

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 7W F-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:31

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on DEC. 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7 cor. common to Sec. 16 & 21, T27N-R7W
 1850 GLO re-survey: B. Ash 9", S35E, 37; Y. Birch 10", N43W, 30.
 1892, E. Mosher, Co. Road Book, visited cor., no witnesses.
 10-20-75, LCRC Liber 1 Pg 369.
 10-29-75, J.L. Fletcher fd 1 3/4" iron pipe, Liber 1 Pg 774 of Surv.
 1-16-76, J.L. Wilcox Liber 1 Pg 886 & 887 of Surv.
 1-20-76, L.L. Cavanagh fd 1 1/4" pipe, Liber 1 Pg 824 of Surv.
 11-11-77, J.L. Fletcher fd 1 3/4" iron pipe/set conc. mon., L.2 Pg 156 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 cor. common to Sec. 16 & 21, T27N-R7W
 Found and accepted conc. mon. on line w/fnc to the North and old E-W fnc to East. As recorded in LCRC Liber 1 Pg 369; Cert of Surv., Liber 2 Pg 156.
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 cor. common to Sec. 16 & 21, T27N-R7W
 Found Conc. Mon. flush to grd. Extended mon. w/ conc. and set 3 1/4" Aluminum Cap in same.
 S33E, 9.57', 12" Dead Birch, fd spk in E. face.
 S63E, 17.43', 12" Cedar, fd spk in E. face.
 N24W, 24.66', 14" Cedar, fd spk in W. face.
 N50E, 75.80', 14" dead Balsam, fd spk in N. face
 West, 48.48', 12" Cherry, fd spk in N. face.
 N40E, 9.0', 8' creek.



Signed by *Eugene Farrier*
 Surveyor's Michigan License No. 24594

Date 12-22-93