

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA

(County)

1993 REMONUMENTATION

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 7W G-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

KALKASKA COUNTY, MICHIGAN RECEIVED

1993 DEC 22 PM 1:31

Joan Hall REG. OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

I, EUGENE FARRIER, in a field survey on DEC. 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-8 cor. common to Sec. 21 & 22, T27N-R7W 1850 GLO re-survey: set post, Hemlock 12", S83E, 17; Hemlock 8", S46W, 7. 2-10-1882, E. Mosher, tied to Corner, no accessories. 1-31-73, J.L. Wilcox, set 1/2" rod, Liber 1 Pg 286 of Surv. 5-10-73, LCRC Liber 1 Pg 232. 8-13-76, J.L. Fletcher, fd 1/2" rod, Liber 1 Pg 917 of Surv. 4-26-83, J.L. Wilcox, fd 1/2" iron, Liber 2 Pg 793 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8 cor. common to Sec. 21 & 22, T27N-R7W Found and accepted 1/2"x24" re-rod w/ obliterated cap, 2.5' East of C/L of Adams road, 1.5' below grd. raised w/nail. GLO witnesses fall in road cut. On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8 cor. common to Sec. 21 & 22, T27N-R7W Found 1/2"x24" re-rod, pulled re-rod and set 5/8"x36" re-bar w/ Brass Cap 0.6' below surface - 25' East of old fnc. and 33' East of cable fnc. N75E, 47.45', 26" Tw. Maple, (fd spk w/tag #20705 NW. fc) S75E, 52.54', 16" Maple clump, (fd spk w/tag #20705 S. fc) S21E, 44.00', 18" Poplar, (fd spk N.E. fc) S48W, 32.08', 24" Tw. Maple, (fd spk SE. fc) N50W, 31.50', 20" Tri. Maple, (fd spk SW fc)

Signed by Eugene FARRIER Surveyor's Michigan License No. 24594

Date 12-22-93

