

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 KALKASKA COUNTY, MICHIGAN RECEIVED

For corners in

Form with fields for KALKASKA (County), 1993 REMONUMENTATION, Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., Recorded Plat, Private Claims.

1993 DEC 22 PM 1:31

Joan Hall REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on DEC. 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column G and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

- G-9 cor. common to Sec. 21, 22, 27 & 28, T27N-R7W
1850 GLO re-survey: set post, Sugar 11", N42E, 42; Hemlock 36", S31W 48.
4-1-69 M.A. Koivistor, MSHD Surv., found 3/4" steel pin.
MSHD, visited cor., plans for M-72, fd 3/4" iron pin, Pg 58 of Sur. BK#1
1-5-73, LCRC Liber 1 Pg 163.
12-10-72, G.R. McKelvey, fd 1/2" iron pipe, Liber 1 Pg 265 of Surv.
9-26-73, LCRC Liber 1 Pg 249.
2-1-74, J.L. Fletcher, fd 1/2" iron pipe, Liber 1 Pg 476 of Surv.
3-29-74, J.L. Fletcher, fd 1/2" iron pipe, Liber 1 Pg 514 of Surv.
4-1-74, J.L. Fletcher, fd 1/2" iron pipe, Liber 1 Pg 515 of Surv.
6-13-79, J.L. Fletcher, fd 1/2" iron pipe, Liber 2 Pg 351 of Surv.
7-29-88, N.B. Livasy, fd 1/2" iron pipe, Cert. of Survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 cor. common to Sec. 21, 22, 27 & 28, T27N-R7W
Found Boat Spike in Mon. Box in C/L M-72, 3' West of C/L Adams road.
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 cor. common to Sec. 21, 22, 27 & 28, T27N-R7W
Found Boat in Mon. Box - Pulled spike and replaced w/5/8"x18" re-rod w/ Brass Cap.
N32E, 60.80', P. Pole, fd nail & tag SE fc.
N17E, 91.60', 10" R. Pine, fd nail & tag W fc.
N12W, 163.50', P. Pole, fd nail & tag E fc.
S62E, 123.42', 12" R. Pine, fd nail & tag SW fc.

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-93

