

FEB 16 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA

(County)

1993 REMONUMENTATION

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>27N</u> R <u>7W</u> | <u>G-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

KALKASKA COUNTY, MICHIGAN
RECEIVED

1993 DEC 22 PM 1:32

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIFER, in a field survey on NOV. 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-11 cor. common to Sec. 27, 28, 33 & 34, T27N-R7W
- 1850 GLO re-survey: set post, Beech 10", N43W, 42; BEECH 7", S82E 31.
- 4-11-1892 E.P. Beebe, Surveyor, visited cor. no accessories.
- 1-5-73, LCRC Liber 1 Pg 162.
- 9-26-73, LCRC Liber 1 Pg 249.
- 7-22-76, J.L. Fletcher, fd 1/2" iron pipe, Liber 1 Pg 904 of Surv.
- 8-26-76, J.L. Fletcher, fd 1/2" iron pipe, Liber 2 Pg 177 of Surv.
- 7-12-79, J.L. Fletcher, fd 1/2" iron pipe, Liber 2 Pg 365 of Surv.
- 10-1-92, B. Feldhauser, fd 1/2" iron pipe, Liber 4 Pg 112 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11 cor. common to Sec. 27, 28, 33 & 34, T27N-R7W
 Found 1/2"x12" iron pipe in C/L of Mitchell & Tyler road. GLO & other witnesses gone due to recent road improvements.
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-11 cor. common to Sec. 27, 28, 33 & 34, T27N-R7W
- Found 1/2"x12" iron pipe - Pulled spike and replaced w/ 5/8"x36" re-rod w/ Brass Cap.
- S58E, 83.42', 12" R. Pine.
- S34E, 70.00', 12" R. Pine, fd.
- N45W, 43.28', "X" in Con. Power Co. Marker.
- N57E, 45.62', "X" in Con. Power Co. Marker.

Signed by Eugene Farrifer
 Surveyor's Michigan License No. 24594

Date 12-22-93