

**SURVEY &
REMONUMENTATION**

KALKASKA COUNTY, MICHIGAN
RECEIVED

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE 95 DEC 27 AM 9:53
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Joan Hill
REC. OF DEEDS

| KALKASKA (County) | Located In: | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1995 REMONUMENTATION | | |
| 1. Public Land Survey | T <u>27N</u> R <u>7W</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on Oct. 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13: Cor. common to Sec. 33 & 34, T27N-R7W, Kalkaska
1850 GLO re-survey: set post, Sugar 12", S25E, 40; Beech 8", S44W, 45.
8-17-1901, W.S. Merrill, Co. Surv, Set stone corner.
8-2-1990, E.D. Farrier, CERT OF SURVEY, fd 3/4" iron pipe, tied crnr.
9-7-1990, LCRC (E.D. Farrier), G-13, fd. 3/4" pipe, L.2 PG.424.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13: Cor. common to Sec. 33 & 34, T27N-R7W, Kalkaska
Fd 3/4" iron pipe, 10' south of c/l of Anderson Rd. & in c/l of 2-track to North. Also, 55' East of c/l of Mitchell Rd. Pulled & replaced with 5/8" x 18" R.B. w/brass cap 0.3' below grade. No GLO wit. were fd. The Kalkaska Co. peer group approved the above monument and is accepted as the best available evidence of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman Eugene Farrier
Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13: Cor. common to Sec. 33 & 34, T27N-R7W, Kalkaska
Fd 3/4" iron pipe. Pulled & replace with 5/8" x 18" R.B. w/brass cap 0.3' below grade.
Set nail & tag S20W, P.P., 58.90'
West, Cor. common to Sec. 3 & 4, T26N-R7W, Kal. Co. Mon., 58.74'
N15W, face yield sign, 42.94'
Set nail & tag S57E, 7" Elm, 61.99'

Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12-22-95



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS