

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN  
RECEIVED

For corners in

<u>KALKASKA</u> <small>(County)</small>	Located In:	Corner Code #:
<u>1993 REMONUMENTATION</u>		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>H-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1993 DEC 22 PM 1:32

*Joan Hall*  
REG OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on DEC. 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7 cor. common to Sec. 15 & 22, T27N-R7W  
1850 GLO re-survey: Set post, Beech 6", S25E, 19; Beech 12", N42W, 28.  
2-10-1882, E Moshes, Co. Surveyor, visited cor., no accessories  
1926 D.P. Smith, Vernon C. Decker Subdivision, Liber A Pg 39.  
2-18-73, LCRC, Liber 1 Pg 299  
6-11-73, J.H. Granger, used corner, Liber 1 Pg 801 of Surv.  
9-29-80, C.F. Roser, D.N.R., fd 3/4" pipe in conc.  
4-26-83, J.L. Wilcox, fd pipe, Liber 2 Pg 791 of surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 cor. common to Sec. 15 & 22, T27N-R7W  
Found and accepted Sq. Conc. Mon. w/ 3/4" gal. pipe 0.4' SW of Alum. sided fnc. N-S in line w/ fnc post to West. Fd accessories.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 cor. common to Sec. 15 & 22, T27N-R7W  
Found and accepted Sq. Conc. Mon. w/ 3/4" gal. pipe, set 3 1/4" Aluminum Cap w/ 1/2"x10" re-rod in center w/ new conc.  
S82W, 31.61', 12" poplar (fd spk N. fc.)  
N41W, 20.76', 14" poplar (fd spk S.W. fc.)  
S39W, 22.40', 10" maple (fd spk S.E. fc.)  
S7E, 13.62', 6" poplar (fd spk W. fc.)



Signed by Eugene Farrier  
Surveyor's Michigan License No. 24594

Date 12-22-93