

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KALKASKA COUNTY, MICHIGAN  
RECEIVED

1993 DEC 22 PM 1:32

*Jean Hall*  
REG OF DEEDS

Register of Deeds Stamp & File Number

<u>KALKASKA</u> (County)	Located In:	Corner Code <del>##</del>
1993 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>H-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EUGENE FARRIER, in a field survey on DEC. 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


H-9 cor. common to Sec. 22 & 27, T27N-R7W  
1850 GLO re-survey: set post, Beech 12", S83E, 17; Hemlock 8", S46W, 7.  
5-14-04, W.S. Merrill, visited cor. (stone) no witnesses.  
MSHD, approx. cor., plans for M-72  
3-29-74, J.L. Fletcher, set 1/2" re-rod, Liber 1 Pg 514 of Surv.  
4-1-74, J.L. Fletcher, fd 1/2" re-rod, Liber 1 Pg 515 of Surv.  
5-17-74, LCRC Liber 1 Pg 312.  
8-26-74, J.L. Fletcher, fd 1/2" re-rod, Liber 1 Pg 631 of Surv.  
9-11-74, J.L. Fletcher, fd 1/2" re-rod, Liber 1 Pg 597 of Surv.  
9-11-74, J.L. Fletcher, fd 1/2" re-rod, Liber 1 Pg 598 of Surv.  
4-25-83, J.L. Fletcher, fd 1/2" re-rod, Liber 2 Pg 793 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 cor. common to Sec. 22 & 27, T27N-R7W  
Found 1/2" re-rod in C/L M-72, 7' +/- W. of N-S tree line w/ fence.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 cor. common to Sec. 22 & 27, T27N-R7W  
Found 1/2" re-rod - pulled & set 5/8"x18" re-rod w/ brass cap in Mon. Box.  
N12E, 37.70', 8" Elm, fd nail & tag E fc.  
N66E, 111.80', 8" W. Pine, fd nail & tag SE fc.  
S10E, 51.68', 24" Maple, fd nail & tag W fc.  
S36E, 122.98', NE cor. garage block foundation.



Signed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 12-27-93