

FEB 18 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

KALKASKA COUNTY, MICHIGAN  
 RECEIVED

1993 DEC 22 PM 1:32

*Joan Hall*  
 REG. OF DEEDS

Register of Deeds Stamp & File Number

Located In:	Corner Code #
KALKASKA (County) 1993 REMONUMENTATION	
1. Public Land Survey	T <u>27N</u> R <u>7W</u> H-11
	T _____ R _____
	T _____ R _____
	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Properly in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____	
5. Private Claims _____	

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, EUGENE FARRIER, in a field survey on NOV. 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-11 cor. common to Sec. 27 & 34, T27N-R7W  
 1850 GLO re-survey: set post, Beech 10", S38W, 30; Sugar 6", N49E 22.  
 9-26-74, LCRC Liber 1 Pg 333.  
 7-23-76, J.L. Fletcher, fd 1/2" re-rod, Liber 1 Pg 904 of Surv.  
 9-19-79, J.L. Fletcher, fd 1/2" re-rod, Liber 2 Pg 486 of Surv.  
 7-23-90, N.B. Livasy, fd 1/2" iron rod, Liber 3 Pg 405 of Surv.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-11 cor. common to Sec. 27 & 34, T27N-R7W  
 Found 1/2"x12" re-rod w/ obliterated cap near road surface. Found con. block with "X" under re-rod. No record of finding GLO witnesses.  
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-11 cor. common to Sec. 27 & 34, T27N-R7W  
 Found 1/2"x12" re-rod - Pulled rod and replaced w/ 5/8"x36" re-rod w/ Brass Cap, 0.8' below road surface in line w/ fnc to South.  
 N45E, 64.96', SE corner of brick house.  
 N26W, 29.84', P. Pole, re-set spk.  
 S37W, 119.52', P. Pole.  
 N71E, 76.17', SW Cor. of 0.7' wide con. wall.

Signed by *Eugene Farrier*  
 Surveyor's Michigan License No. 24594

Date 12-22-93

