

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (KALKASKA), Located In, Corner Code (I-9), and numbered items 1-5 describing the survey and property.

KALKASKA COUNTY, MICHIGAN RECEIVED

1993 DEC 22 PM 1:32

Signature of Joan Hall, REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot in cell G9.

I, EUGENE FARRIER, in a field survey on DEC. 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-9 cor. common to Sec. 22, 23, 26 & 27, T27N-R7W
1850 GLO re-survey: set post, Sugar 19", S20E, 03; Sugar 12", N18W, 50
6-15-1883, E. Mosher, Co. Surv., tied cor. for highway survey.
6-28-1892, E. Mosher, Co. Surv., tied cor. for highway survey.
4-10-03, W.S. Merrill, Co. Surv., used cor., Maple 5" S36E, 62; Maple 6" S41W, 37.
11-9-03, W.S. Merrill, Co. Surv., used cor. (stone) for survey in NW/4 Sec. 26.
1907 W.S. Merrill, Co. Surv., used cor. (stone) for survey in SER/4 Sec. 22.
MSHD used cor. for survey of M-72
9-20-73, N.F. Parker, used cor. for survey. Liber 1 Pg 393 of Surv.
9-26-73, LCRC Liber 1 Pg 249.
8-26-74, J.L. Fletcher, fd 1" bolt, Liber 1 Pg 630 of Surv.
8-26-74, J.L. Fletcher, fd 1" bolt, Liber 1 Pg 631 of Surv.
9-11-74, J.L. Fletcher, fd 1" bolt, Liber 1 Pg 597 of Surv.
9-11-74, J.L. Fletcher, fd 1" bolt, Liber 1 Pg 598 of Surv.
9-26-74, LCRC Liber 1 Pg 333.
2-27-75, J.L. Fletcher, fd 1" bolt, Liber 1 Pg 654 of Surv.
7-77, A.L. Dragoo, fd iron rod, Liber 2 Pg 30 of Surv.
11-15-77, J.L. Fletcher, fd 1" bolt, Liber 2 Pg 142 of Surv.
3-29-78, J.I. Nelson, fd bolt, Liber 2 Pg 180 of Surv.
7-6-83, A.L. Dragoo, used cor., Liber 2 Pg 779 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 cor. common to Sec. 22, 23, 26 & 27, T27N-R7W
Found 1"x24" carriage bolt in Mon. Box, 2" South of C/L of M-72 and 2' South of C/L of Saunders road.
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 cor. common to Sec. 22, 23, 26 & 27, T27N-R7W
Found 1"x24" carriage bolt in Mon. Box - Pulled bolt and replaced w/ 5/8"x36" re-rod w/ Brass Cap in Mon. Box.
N32E, 60.92', 12" fence post, fd spk in NW fc.
N25W, 48.30', 6' P. Pole, fd spk & tag in W. fc.
S22W, 106.87', 10" Spruce, fd spk w/tag W. fc.
S35E, 93.45', 8" Scotch Pine, fd spk w/tag SW fc.

Signed by Eugene Farrier Date 12-27
Surveyor's Michigan License No. 24594



MICHIGAN STATE BOARD OF SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983