

**SURVEY &  
REMONUMENTATION**

FEB 18 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>I-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALKASKA COUNTY, MICHIGAN  
RECEIVED

1993 DEC 22 PM 1:32

*Joan Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on NOV. 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-10 cor. common to Sec. 26 & 27, T27N-R7W  
 1850 GLO re-survey; set post, Hemlock 10", N19E, 38; Sugar 12", S51W, 29  
 11-9-03, W.S. Merrill, Co. Surv., fd cor., Elm Shade tree 10" S53E 13.  
 8-26-74, J.L. Fletcher, set 1/2" re-rod, Liber 1 Pg 630 of Surv.  
 8-26-74, J.L. Fletcher, set 1/2" re-rod, Liber 1 Pg 631 of Surv.  
 9-26-74, LCRC Liber 1 Pg 333.  
 2-27-75, J.L. Fletcher, 1/2" re-rod, Liber 1 Pg 654 of Surv.  
 7-77, A.L. Drago, fd iron rod, Liber 2 Pg 30 of Surv.  
 9-19-79, J.L. Fletcher, fd 1/2" re-rod, Liber 2 Pg 486 of Surv.  
 7-23-90, N.B. Livasy, fd 1/2" iron rod, Liber 3 Pg 405 of Surv.  
 3-5-91, N.L. Way, fd 1/2" iron rod, Liber 3 Pg 476 of Surv.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

I-10 cor. common to Sec. 26 & 27, T27N-R7W  
 Found 1/2"x12" re-rod w/ obliterated cap, 3' West of C/L of Saunders road.  
 No GLO witnesses available due to road improvement.  
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-10 cor. common to Sec. 26 & 27, T27N-R7W  
 Found 1/2"x12" re-rod - Pulled rod and replaced w/ 5/8"x18" re-rod w/  
 Brass Cap in Mon. Box.  
 N85W, 32.48', P. Pole, fd.  
 N70W, 46.55', 16" Beech, set spk.  
 N35W, 53.88', 16" Maple, fd.  
 S64E, 69.75', P. Pole, fd.  
 S72W, 23.08', 8" Elm, fd.



Signed by Eugene Farrier  
 Surveyor's Michigan License No. 24594

Date 12-22-93