

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 RE-MONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALASKA COUNTY, MICHIGAN  
RECEIVED

1993 DEC 22 PM 1:33

*Joan Hall*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on NOV. 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


K-7 cor. common to Sec. 13, 14, 23 & 24, T27N-R7W  
1850 GLO re-survey: set Hem. post Sugar 20", N30E, 46; Beech 14", S15W, 65  
7-7-1899, W.S. Merrill, Co. Surv., tied cor. for survey in SW/4 Sec. 13.  
4-26-00, W.S. Merrill, Co. Surv., used cor. for survey in SW/4 Sec. 13.  
4-18-13, W.S. Merrill, Co. Surv., used cor. for highway survey in SW/4 Sec. 14.  
6-8-73, LCRC Liber 1 Pg 205.  
5-21-75, LCRC Liber 1 Pg 351.  
11-75, A.L. Dragoo, fd iron rod, Liber 1 Pg 770 of Surv.  
1977, A.L. Dragoo, fd iron, Liber 2 Pg 199 of Surv.  
4-28-78, L.M. Gerschbacher, survey for Shell Oil Company.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 cor. common to Sec. 13, 14, 23 & 24, T27N-R7W  
Found 1/2"x8" re-bar in Mon. Box, 2" North of C/L of Kettle Lake road and 3.5' West of C/L of Aller road. Last LCRC & GLO witnesses were not recovered - due to road improvements.  
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 cor. common to Sec. 13, 14, 23 & 24, T27N-R7W  
Found 1/2"x8" re-bar in Mon. Box - Pulled re-bar and replaced w/ 5/8"x18" re-rod w/ Brass Cap in Mon. Box.  
N17E, 131.53', P. Pole, fd.  
S58E, 63.85', 14" Maple, fd.  
S18E, 99.55', P. Pole, fd.  
S50W, 54.28', E'ly Savoy Gas Marker (c/l) set.



Signed by *Eugene Farrier*  
Surveyor's Michigan License No. 24594

Date 2-93