

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KALKASKA</u> (County)	Located In:	Corner Code #
1993 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

KALKASKA COUNTY, MICHIGAN
 RECEIVED

1993 DEC 22 PM 1:33

Jean Hall
 REG. OF DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on NOV. 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 cor. common to Sec. 23 & 24, T27N-R7W
 1850 GLO re-survey: set post, Sugar 14", N42E, 37; Sugar 12", S81W, 51
 7-29-1889, E. Mosher, Co. Surv., used cor. for highway survey in Sec. 23
 1903, W.S. Merrill, Co. Surv., used cor. for survey in NE/4 Sec. 23.
 9-13-71, P.G. Perla, fd 1" pipe, Liber 1 Pg 46.
 6-15-73, P.G. Perla, fd 1" pipe, Liber 1 Pg 341.
 4-30-74, L.J. Czubak, fd 1" iron pipe. Liber 1 Pg 545.
 5-21-75, LCRC Liber 1 Pg 351.
 8-28-87, N.B. DeYoung, fd 3/4" iron pipe, Liber 3 Pg 161 of Surv.
 4-28-78, L.M. Gerschbacher, survey for Shell Oil Company.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 cor. common to Sec. 23 & 24, T27N-R7W
 Found 3/4" iron pipe in C/L of Aller road, 4' North of fnc line to West.
 Iron pipe rotted out.
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 cor. common to Sec. 23 & 24, T27N-R7W
 Found 3/4" iron pipe rotted out - reset w/ 5/8"x18" re-rod w/ Brass Cap
 0.6' below grd.
 N85W, 38.77', 10" Maple clump, fd.
 S39W, 121.16', P. Pole, fd.
 N82W, 33.25', 1/2" re-bar w/DeYoung cap, fd.
 S78E, 35.75', Pipeline vent riser, set.

Signed by *Eugene Farrier* Date 12-22-93
 Surveyor's Michigan License No. 24594

