

SURVEY &
REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN
RECEIVED

95 DEC 27 AM 9:53

For corners in **COMMISSION**

<u>KALKASKA</u> (County)	Located in:	Corner Code #
1995 REMONUMENTATION		
1. Public Land Survey	T <u>27N</u> R <u>7W</u>	<u>K-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Joan Stone
REG. DEEDS

Register of Deeds Stamp & File Number

I, EUGENE FARRIER, in a field survey on Oct. 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2			5		4		3		2			
3												
4	7		8		9		10		11			
5												
6	16		17		18		15		14			
7												
8	19		20		21		22		23			
9												
10	30		29		28		27		26			
11												
12	31		32		33		34		35			
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13: Cor. common to Sec. 35 & 36, T27N-R7W, Kalkaska
1850 GLO re-survey: set cor. post, Cdr 12", N74E, 18; Cdr 6", N28W, 23.
2-12-1901, W.S. Merrill, Set stake, no accessories.
8-23-1974, LCRC(J.L. Fletcher), K-12, Set rerod, L.1 PG.332, by single PRO along township line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13: Cor. common to Sec. 35 & 36, T27N-R7W, Kalkaska
Fd 1/2" R.B. w/cap, 10' East & 5' North of c/l of intersection of Anderson Rd. & Golden Rd. Pulled and replaced with 5/8" x 18" R.B. w/brass cap 0.3' below Rd. Surface. No GLO witnesses were found. The Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

Ratified by Peer Group
P.A. 345 - 1990 Kalkaska County
Chairman *Eugene Farrier*
Date 12-19-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13: Cor. common to Sec. 35 & 36, T27N-R7W, Kalkaska
Fd 1/2" R.B. w/cap. Pulled and replaced with 5/8" x 18" R.B. w/ brass cap 0.3' below Rd. Surface.
Set nail & tag, N40W, P.P., 71.66'
Set nail & tag, N24E, Service Pole, 47.90'
Set nail & tag, S32W, Service Pole, 116.11'
Set nail & tag, S62W, Face of Rd. sign, Anderson & Golden Rds., 56.83'
West, Cor. common to Sec. 1 & 2, T26N-R7W, Kal.Co.Mon, 27.72'

Signed by *Eugene Farrier*
Surveyor's Michigan License No. 24594

Date 12-22-95

