

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

KALKASKA COUNTY, MICHIGAN RECEIVED

For corners in

Table with columns: KALKASKA (County), 1993 REMONUMENTATION, Located in: (Town/Range), Corner Code. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

1993 DEC 22 PM 1:35

Signature of Joan Hall, REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, EUGENE FARRIER, in a field survey on NOV. 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36 and a dot at row 7, column L.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 cor. common to Sec. 13 & 24, T27N-R7W
1850 GLO re-survey: set Hem. post Hemlock 18", N30E, 30; Beech 10", S89E, 21.
7-7-1899, W.S. Merrill, Co. Surv., tied cor. for survey in SW/4 Sec. 13.
4-26-00, W.S. Merrill, Co. Surv., original bearing trees of Gov't Re-survey.
11-9-23, W.S. Merrill, Co. Surv., one Gov't bearing tree stump, Hemlock 16" N27W, 21; Hemlock 14", S30W, 35.
11-71-75, LCRC Liber 1 Pg 343.
9-8-75, LCRC Liber 1 Pg 359.
9-8-75, N.F. Parker, Liber 1 Pg 703.
11-75, A.L. Dragoo, iron rod, Liber 1 Pg 770 of Surv.
12-4-75, J.L. Wilcox, 1" pipe, Liber 1 Pg 896 of Surv.
1977, A.L. Dragoo, iron rod, Liber 2 Pg 199 of Surv.
4-28-78, L.M. Gerschbacher, found 5/8" re-bar, Liber 2 Pg 240 of Surv.
4-25-79, J.L. Wilcox, 1" pipe, Liber 2 Pg 511 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-7 cor. common to Sec. 13 & 24, T27N-R7W
Found 1" Galvanized pipe x 48" w/ 1/2" re-rod in center. 2' North of gravel C/L of Kettle Lake road. GLO witnesses fell in road cut area.
On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 cor. common to Sec. 13 & 24, T27N-R7W
Found 1" Galvanized pipe x 48" w/ 1/2" re-rod in center - pulled same and set 5/8"x36" re-rod w/ Brass Cap 0.6' below surface.
N18E, 33.90', 18" Beech, fd.
N60E, 57.97', 30" Hemlock fd.
S40E, 52.89', 28" Maple fd.
S23W, 61.27', 12" Hemlock set.



Signed by Eugene Farrier
Surveyor's Michigan License No. 24594

Date 12/23

FORM 200

MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983