

FEB 18 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

KALKASKA

(County)

1993 REMONUMENTATION

Located In:

Corner Code #

- 1. Public Land Survey T 27N R 7W M-7
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

KALKASKA COUNTY, MICHIGAN RECEIVED

1993 DEC 22 PM 1:35

Jean Hall
REG. OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, EUGENE FARRIER, in a field survey on NOV. 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | I |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

M-7 cor. common to Sec. 13 & 24, T27N-R7W & Sec. 18 & 19, T27N-R6W
 1850 GLO re-survey: set new post in place of the old, Hemlock 14", S34W, 37'; Hemlock 9", N9W, 52 page 151 of records and Hemlock 15", S9W, 17'; Hemlock 8", N68.5W, 42 page 139 of records.
 5-6-1901, Co. Surv. indicates distance to cor. for survey in SW/4 Sec. 18.
 4-26-00, W.S. Merrill, Co. Surv., indicates distance to cor. from 1/4 cor. to North.
 11-9-23, W.S. Merrill, Co. Surv., Birch 7, N3W, 28.5.
 11-75, A.L. Drago, iron rod, Liber 1 Pg 770 of Surv.
 12-4-75, J.L. Wilcox, 1/2" rod, Liber 1 Pg 896 of Surv.
 12-5-75, LCRC Liber 1 Pg 383.
 1977, A.L. Drago, iron rod, Liber 2 Pg 199 of Surv.
 4-28-78, L.M. Gerschbacher, found 5/8" re-bar, Liber 2 Pg 240 of Surv.
 4-25-78, J.L. Wilcox, see wit. Liber 1 Pg 896. Liber 2 Pg 511 of Surv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 cor. common to Sec. 13 & 24, T27N-R7W & Sec. 18 & 19, T27N-R6W
 Found and accepted 5/8" re-bar in C/L intersection of Kettle Lake road and Rosenberg road. GLO witnesses fell in road area.
 On 12-16-93 the Kalkaska Co. peer group approved the above monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 cor. common to Sec. 13 & 24, T27N-R7W & Sec. 18 & 19, T27N-R6W
 Found 5/8" re-bar - could not remove, drove 5/8"x18" re-rod w/ Brass Cap over it.
 S56E, 43.68', 16" Tri. Maple, set.
 N56E, 32.22', 24" W. Pine, fd.
 S59W, 50.48', Stop sign Post.
 S85E, 32.96', 1/2" re-bar w/cap #24594, fd.
 N29W, 71.86', P.Pole, fd.

Signed by *Eugene Farrier*

Date 12-22-93

Surveyor's Michigan License No. 24594

