

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KALKASKA
 (County)

Located In: _____ Corner Code ~~##~~ _____

1. Public Land Survey	T	<u>27N</u>	R	<u>7W</u>	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	<u>9</u>	T	_____	<u>12</u>
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
 2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

CARL F. ROSER, in a field survey on JUNE 15, 19 94,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:
 9

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 9

FOUND 1/2" REROD FOR THE SW CORNER OF N1/2 OF SE1/4 OF SEC. 9, AS SET BY GRANGER ENG. (RECORDED LI. 2, PG. 573), RLS J.FLETCHER. DROVE 1/2" X 30" REROD, ON S. LINE OF N1/2 OF SE1/4, N89°52'E, 559.0'.

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 9

FD 1/2" REROD W/PS CAP, ADDED CEDAR POST W/LOCATION TAG.
 6"W.PINE N50°W 1.43'
 18°R.PINE N10°E 18.95'
 17°MAPLE S80°E 13.09'
 6"W.PINE S35°W 10.21'
 FD 1/2" IRON BY J.FLETCHER N89°52'E 979.23'



1= MIT. BY OTHERS

Signed by Carl F. Roser

Date 6-15-94

Surveyor's Michigan License No. 12028