

**SURVEY &  
REMONUMENTATION**

**FEB 13 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>KALKASKA</u>	Located In:	Corner Code #
(County)		
1997 REMONUMENTATION		
1. Public Land Survey	T 26N R 8W	M-1
	T 27N R 8W	M-13
	T 26N R 7W	A-1
	T 27N R 7W	A-13
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, EUGENE FARRIER, in a field survey on OCTOBER 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
M-1: Sec. Cor. Common to Sec. 1, T26N-R8W, Boardman Twp. & Sec. 36, T27N-R8W, Kalkaska Twp., & Sec. 6, T26N-R7W, Orange Twp. & Sec. 31, T27N-R7W, Kalkaska Twp.  
GLO resurvey, set cedar post, 9" Beech, N61W 25, 9" Beech, S63E 17  
06-13-1902, County Surveyor, used cor., no accessories  
05-17-1971, J.F. Erickson #16929, LCR, Fd. 1" pipe 2" below C/L gravel Rd. w/accessories Lib 1, Pg. 36  
06-17-1980, A.L. Dragoo #3921, Cert. Survey, Fd. iron pipe w/accessories, Lib. 2, Pg. 565  
10-26-1982, A.L. Dragoo #3921, Cert. Survey, noted cor. w/accessories, Lib. 2, Pg. 741  
08-22-1983, Farrier Surveying, #6383 field notes, Fd. 3/4" pipe  
08-08-1984, Farrier Surveying, Cert. Survey, (noted cor. & accessories Lib. 2, Pg. 698)  
05-27-1987, C.F. Roser #12028, LCR, Fd. 3/4" iron pipe w/accessories, Lib. 2, Pg. 348  
07-06-1992, Grand Traverse Surveying, Cert. Survey, Fd. 3/4" iron pipe w/accessories, Lib. 4, Pg. 77



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M-1: Sec. Cor. Common to Sec. 1, T26N-R8W, Boardman Twp. & Sec. 36, T27N-R8W, Kalkaska Twp., & Sec. 6, T26N-R7W, Orange Twp. & Sec. 31, T27N-R7W, Kalkaska Twp.  
Fd. 3/4" x 18" iron pipe 5' South of C/L Thomas Rd. Pulled & replaced with 5/8" x 18" rebar w/brass cap in mon box. No GLO witnesses were fd. The Kalkaska Co. Peer group approved and accepted the above monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-1: Sec. Cor. Common to Sec. 1, T26N-R8W, Boardman Twp. & Sec. 36, T27N-R8W, Kalkaska Twp., & Sec. 6, T26N-R7W, Orange Twp. & Sec. 31, T27N-R7W, Kalkaska Twp.  
Fd. 3/4" x 18" iron pipe 5' South of C/L Thomas Rd. Pulled & replaced with 5/8" x 18" rebar w/brass cap in mon box.  
Fd. Nail North, DNR post w/tag 38.09'  
Fd. Nail N36E, 10" Maple 46.75'  
Set nail & tag S38W, 10" R. Pine 49.55'  
South, iron & cap #24594 27.27'

Ratified by Peer Group  
P.A. 345 - 1990 Kalkaska County  
Chairman Eugene Farrier  
Date 1-29-98

Signed by Eugene Farrier Date 2-3-98  
Surveyor's Michigan License No. 24594



**3004876**  
Page: 1 of 1  
02/04/98 11:22I

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN., 1983  
REVISED OCT., 1995