

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KALKASKA

(County)

Located In:

Corner Code ≠

1. Public Land Survey	T	<u>27N</u>	R	<u>BW</u>	<u>J-9, K-9,</u>
	T		R		<u>K-10, K-11</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL KIISKILA, in a field survey on SEPT. 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9

K-9

K-10

(NO EVIDENCE OF G.L.O. CORNER, B.T.'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. CONT.-- PS #30079 Li.2,
 Pg.380 OF LCRC'S. COR AT
 W.EDGE RD IN CURVE(N & SE'LY)
 & AT SOUTH EDGE 2-TRACK EAST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9

K-9

K-10

K-11

REESTABLISHED THE N1/4 COR OF SEC 26 MIDWAY AND ON LINE BETWEEN FOUND SEC. CORNERS. THIS COR. WAS PREVIOUSLY SET AT THIS POSITION BY P.S. J.WILCOX BUT WAS REMOVED DURING A CLEAR CUT. CORNER FALLS IN S'LY EDGE OF LARGE CLEAR-CUT WHICH HAS BEEN PLANTED WITH RED PINE.

FD & ACCEPTED 1/2" IRON ROD SET BY N.PARKER, PS #16939, W/PS CAP FOR NE COR. S-26. BELIEVED IRON TO BE THE SAME POSITION AS MONUMENTED BY M.SCHAAF(CONS. DEPT. FORESTER & SUR.) & LATER REWITNESSED BY MI. CONS. DEPT. SUR. IN JAN. 1952 (ONE ORIGINAL B.T. STILL IN PLACE IN FAIR CONDITION AT THAT TIME). COR ALSO RECORDED BY P.CASE, - CONT. ABOVE-

FD. AND ACCEPTED 1/2" IRON ROD W/PS CAP FOR E1/4 S-26, AS SET BY P.S. J.WILCOX, IN 1978, MIDWAY AND ON LINE BETWEEN SECTION CORNERS.

FD. AND ACCEPTED 1/2" REROD FOR THE SE COR. OF SEC. 26. THIS CORNER ALSO WAS ACCEPTED AND WITNESSED BY P.S. J.WILCOX IN 1978, LIBER 2, PAGE 195.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9

K-9

K-10

K-11

FD 1/2" REROD LYING ON GROUND, SET 1"x 32" IRON PIPE W/CAP & CARSONITE POST.

FD 1/2" CAPPED IRON, SET 1" PIPE W/CAP OVER IR.
 #18" R.PINE N61°W 60.96'
 #8" J.PINE S82°W 35.01'
 6" J.PINE S70°E 38.73'
 4" R.PINE N41°E 82.10'
 SET CARSONITE POST WEST 33'

FD 1/2" CAPPED IRON, SET DNR MON OVER IRON & SET CARSONITE POST.
 #10" J.PINE N42°E 29.17'
 #12" J.PINE N15°E 18.60'
 #12" J.PINE N32°W 27.18'
 #11" J.PINE S86°W 34.17'

FD. 1/2" REROD & SQUARE TOP POST, SET DNR MON.
 #8" MAPLE N55°W 16.31'
 #10" MAPLE N05°E 22.92'
 #14" TW.MAPLE S05°W 19.02'
 #9" MAPLE N82°E 20.22'

*=P.CASE,P.S. WIT. Li.2.Pg.380

*=J.WILCOX WIT, Li.2, Pg.195

*= J.WILCOX WIT, Li.2,Pg.195

Signed by

Carl T. Kiiskila

Date

12-7-95

Surveyor's Michigan License No. _____

33981

