

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 17-20

CORNER MONUMENT Set Cons. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 10/4/67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

4" W. Pine N 33 E 14.6'

8" H. Maple N 57 W 9.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between Section corners, during a survey of Section 20. No U.S. evidence left. A well point was found about 25' WSW from our corner which probably was established by Harold Preston in a partial survey, which was done to mark the approximate boundary of the S $\frac{1}{2}$ of SE $\frac{1}{4}$, Sec. 17.

Could find no valid reason for placing corner anywhere but midpoint. Believe we have recovered Merrill's section corners at each end of this sectionline. This position conforms best to existing occupation in Section 20 subdivision.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 10/4/67
REGISTERED LAND SURVEYOR #10068