

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 27 N.R. 8 W  
T. 27 N.R. 9 W


Kalkaska  
Grand Traverse COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 7 - 12

CORNER MONUMENT Set 1" pipe with 4" aluminum cap below surface

DATE MONUMENT PLACED AND WITNESSED 4-13-67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

24" H. Maple S 25 E 24.7'

5" R. Pine N 40 W 56.7'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a survey in this township. Recovered corner, marked with a stone with cross on top, as established or identified by Merrill in 1909 survey. Falls in line with roads east and west and fence line south. Checks very well for line and distance to good corner north.

SURVEYOR'S SEAL

SIGNED \_\_\_\_\_ DATE 4-25-67

REGISTERED LAND SURVEYOR #10068