

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16 - 17

CORNER MONUMENT Set 1" pipe with 4" Alum. cap below surface

DATE MONUMENT PLACED AND WITNESSED 4-27-67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

6" Cherry N 74 E 56.6'

5" R. Oak S 75 E 61.0'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement between section corner north and meander corner south, according to a record of survey by E. B. Dennis in 1895, in which he recovered original M.C. and Section corner and reestablished this corner by proportionate measurement. Could find no monument, probably destroyed in road construction.

SURVEYOR'S SEAL

SIGNED _____ DATE 4-27-67

REGISTERED LAND SURVEYOR #10068