

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15-16

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4-18-67

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED


12" W. Pine S 5 W 32.8'

5" W. Pine S 75 E 51.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a retracement of this area. Found stake bottom, as established by Merrill in early 1900's. One probable U.S.B.T. stump remnants in place, and Merrill's witness NE.



SURVEYOR'S SEAL

SIGNED _____ DATE 4-25-67

REGISTERED LAND SURVEYOR #10068