

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections 4-5-8-9

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4-6-67

WITNESSES TO CORNER.....



8" H. Maple N 48 E 3.8'

12" H. Maple N 30 W 32.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restered by occupational evidence of old fence lines N-S-E-W, and evidence of old road grade north. Check very well for distance in all directions. Could find no previous corner, but consider this best available evidence.

SURVEYOR'S SEAL

SIGNED _____ DATE 4-24-67
REGISTERED LAND SURVEYOR #10068