

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 27 N.R. 8 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections 2-3-10-11

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4-6-67

WITNESSES TO CORNER.....



6" H. Maple S 79 E 29.3'


10" H. Maple S 80 W 75.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by double proportionate measurement between corners one mile east, two miles west, 1/2 mile north and 1 1/2 miles south, while making a survey in this township. Corner falls in old township road grade N-S and checks good for distance all directions. Nothing left for U.S.B.T.s.



SURVEYOR'S SEAL

SIGNED _____ DATE 4-24-67
REGISTERED LAND SURVEYOR #10068