

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska (County)	Located In	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S 30. T 27N R 8W	9	
	S 30 T 27N R 8W	13	
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on July 9, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30	●		29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

9 - None



13 - Rec. Survey L. 1, P. 850 - J.L. Fletcher - 1975

Set iron.

- Unrecorded survey - Mitchell & Assoc. File #950615 - 1995 - iron set

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

9 - CE 1/16 cor. Sec. 30 - Set 2" Alum. Cap on 5/8" x 34" Rebar per standard BLM procedure. Centerline of NNE-SSW Gravel Rd. is 87'± W.

13 - SE 1/16 cor. Sec. 30 - Fd. 1/2" x 18" capped rebar #28417-30079 per Mitchell Survey in close agreement with calculated position. Mitchell CIR accepted as the best available evidence of the position of the corner.

Reference Pt. - Fd. 1/2" capped iron per Fletcher is S38°40'E 15.81' of '13'. Iron's position based on rejected Government corner positions and is not utilized as '13' in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

9 - 2" AC on 5/8" x 34" Rebar
 N20°W 23.13' to N & T in E. side light pole
 S67°W 29.98' to NE cor. of HSE #639
 S26°W 38.61' to face 3" iron swing pole
 N8°E 87.77' to N & T in E. side 4" Fir
 NE 1' to set blue carsonite post with location tag

13 - Replaced 1/2" CIR #24817 - 30079 with 2" Alum. Cap on 5/8" x 34" Rebar.
 NE 1' to set blue carsonite post with location tag.
 N86°E 2.53' to set N & T in SW side 16" R. Pine
 South 12.91' to set N & T in E side 18" R. Pine
 N78°W 16.24' to set N & T in S side 11" R. Pine
 N39°55'W 9.72' to Fd. 3/4" iron pipe
 S38°40'E 15.81' to Ref. Pt. - 1/2" CIR
 N63°E 12.09' to Fd. 1/2" CIR #19830

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 10/2/2002