

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Kalkaska Located In _____ Corner Code # _____
 (County)

1. Public Land Survey T 27N R 8W 1-5
T _____ R _____
2. Property Controlling in Section S 16 T 27N R 8W 9
S _____ T _____ R _____
3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____
 5. Private Claims: _____

1. Craig W. McVean, in a field survey on May 5, 20 04 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- L-5 - GLO - Set post - L. Lyon - 1850 9 - CSR - W. S. Merrill - 1903
 Hem. 16" N28°W 34 L. Pine 10" S25°E 3 L.
 Hem. 10" S10°W 30 L.
 - M. Schaaft - 1933 - Random W. between 11 & 14 - 80 CH. Intersect Sec. Cor. 62 L. N. of post. Ch was 18 L. long. Random N. between Sec. 14 & 15. 80 CH stake at Rd. E & W. Intersected Sec. Cor. set by measurement 54 L. E. of post. Chain was 28 L. long.
 - DNR Cor. record -- K. J. Ostling - 1967 -
 Set 1" pipe with 4" Alum. Cap by double proportion while making a survey in this area. Unable to recover any previous corner and USBT all gone. Position falls in line with old fire Lines S & W, and checks good for distance all directions.
 4" R. Pine N22°W 43.8'; 5" R. Pine S55°E 62.2'.



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-5 - Sec. Corner common to Sec. 10, 11, 14 & 15 - Fd. 4" DOC 9 - CE 1/16, Sec. 16 - No conclusive evidence of Merrill's position.
 (DNR) Alum. Cap on 1" iron pipe near surface - 5" N. of Fd. Pine slip. in area and dug per record bearing and distance intersect of T. Inter. of firelines E, W & S. DOC Mon. but nothing. Set stamped 2" Alum. Cap on 5/8" x 3/4" iron rebar per Standard BLM procedure.
 accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 - Lowered DOC (DNR) Mon. - 0.5' 9 - 2" Alum. Cap on 5/8" x 3/4" rebar.
 N24°W 43.79' to set N & T in E. side 12" R. Pine (KJO) Set Blue Carsonite Post 1" W.
 S56°E 62.56' to set N & T in S. side 14" R. Pine (KJO) S35°E 16.57' to set N & T in NE side 6" S. Maple
 N60°E 29.18' to set N & T in S. side 10" W. Pine N44°W 14.48' to set N & T in W. side 8" S. Maple
 S40°W 26.35' to set N & T in NW side 6" W. Pine S12°W 11.15' to set N & T in W. side 10" S. Maple
 Set Blue Carsonite Post w/loc. Tag 33' N S70°W 19.44' to set N & T in S. side 14" S. Maple

Signed by: Craig W. McVean Date: 12/16/2005
 Surveyor's Michigan License No.: 39088