

# LAND CORNER RECORDATION CERTIFICATE

## Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 Kalkaska \_\_\_\_\_  
 (County)

1. Public Land Survey  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section  
     S 16 T 27N R 8W 6  
     S 16 T 27N R 8W 7
3. Miscellaneous Property in Section  
     S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
     S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

1. Craig W. McVean, in a field survey on May 3, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:  
 6 - None Z - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 6 - NE 1/16<sup>th</sup> Corner - Section 16, T27N, R8W - Set 2" Alum. Z - N 1/16<sup>th</sup> Corner common to Sec. 16 & 15, T27N, R8W - Set 2" Alum. Cap on 5/8" x 3/4" rebar per standard BLM procedure.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 6 - Set 2" Alum. Cap on 5/8" x 3/4" rebar. Z - Set 2" Alum. Cap on 5/8" x 3/4" rebar.  
     N15°W 29.65' to set N & T in W. side 10" Oak N27°W 10.98' to set N & T in W. side 7" S. Maple  
     S57°W 13.35' to set N & T in S. side 5" S. Maple N82°E 17.79' to set N & T in S. side twin 14" R. Maple  
     S52°E 14.47' to set N & T in SW side Twin 10" Oak S16°E 16.14' to set N & T in E. side 5" W. Pine  
     N45°E 27.96' to set N & T in SE side 12" Oak clp. of 4 N80°W 35.58' to set N & T in N. side 8" R. Maple  
     Set blue carsonite post with location tag 1' NW Set blue carsonite post with location tag 1' NE

Signed by: *Craig W. McVean* Date: 12/16/2005  
 Surveyor's Michigan License No.: 39088