

# LAND CORNER RECORDATION CERTIFICATE

## Filing Requirement of Act 74, Mich. PA 1970

For Corners In: \_\_\_\_\_ Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 Kalkaska (County)

1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling in Section S 16 T 27N R 8W 13
- S 16 T 27N R 8W 14
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

1. Craig W. McVean, in a field survey on Aug. 12, 20 04, do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

13 - None

14 - Rec. Sur. - L. 3, p. 141 - J. L. Wilcox - 1987 - Set



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

13 - SE 1/16, Sec. 16 - Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per Standard BLM procedure.

14 - S 1/16 Corner common to Sec. 16 & 15 - Fd. 1/2" capped iron # 14102 that is N2°52' W 2.02' of calculated position. Wilcox has distance of 2640.73' vs. 2635.87' - M - Grid between 'G6' and 'G7'. Thus reject 1/2" CIR and set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13 - 2" Alum. Cap on 5/8" x 34" iron rebar  
 N50°E 17.56' to set N & T in NW side 10" W. Pine  
 S22°E 45.14' to set N & T in E. side 7" W. Pine  
 S45°W 16.94' to set N & T in NW side 12" W. Pine  
 N10°W 3.11' to set N & T in W. side 6" Cherry  
 Set Blue Carsonite Post 1' SW

14 - Stamped 2" Alum. Cap on 5/8" x 34" iron rebar.  
 Set Blue Carsonite Post w/ loc. tag 1' NW  
 N17°W 23.36' to set N & T in W. side 6" W. Pine  
 S65°E 17.72' to set N & T in S. side 8" W. Pine  
 S2°W 22.91' to set N & T in W. side 20" W. Pine  
 N88°W 28.54' to set N & T in S. side 6" W. Pine  
 N2°52'W 2.02' to fd. 1/2" CIR # 14102

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 12/16/2005