

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>6</u> R. <u>6</u> ● W.	<u>B-9; B-11; C-9</u>
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	, T. <u>28</u> N. ● R. <u>6</u> W.	<u>2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 2, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

2

Drove 1 1/4"x18" Rod
 10" Maple Clstr. N69°E 35.9
 8" Twn. Maple N72°W 62.3
 8" Maple S70°W 27.4
 Ctr. E-W dirt rd. Due N 3'±
 Set cedar post w/loc. tag
 Due S 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-9 Found 1/2" rerod with RLS Cap #20706, Corey Hughes, buried at S edge of E-W dirt road.
- B-11 Found 3/4" rerod by RLS L. Gerschbacher. Section corner code B-11 dated April 21, 1975.
- C-9 Recovered 1/2" rod by RLS J. Wilcox; in approximate center of E-W dirt road.
- 2 Set 1/16 corner S.P.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9	B-11	C-9
Fd. 1/2" rerod w/RLS Cap	Fd. 3/4" rerod & set cedar post w/loc. tag	Fd. 1/2" rod beside 1 1/2"x4" plow iron
28" Maple S25°W 16.76	20" W.Pine S43°E 42.75	10" Maple N75°E 49.39
10" Maple N59°W 66.00	16" Hemlock S56°W 31.25	30" Twn. Maple N29°W 42.30
9" Twn. Maple N16°W 60.18	12" Hemlock N35°E 49.34	15" Maple S09°E 33.70
Ctr. E-W dirt rd. Due N 15'±	Ctr. E-W swp. trail road	Set cedar post w/loc. tag
Set ced. post w/loc. tag	Due N 18'±	Due S 33'
Due S 33'		

SIGNED BY Carl F. Roser

DATE 10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

COLD SPRINGS TOWNSHIP
KALKASKA COUNTY