

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>25</u> , T. <u>28</u> ,	N. _____ S., R. <u>7</u> _____ E. _____ W. _____	<u>10;11;13;14;16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 12, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. - Description of original monument and accessories and/or subsequent restoration-~~

C. (continued)

14	16
Set ½"x60" Iron Bar & cedar post w/loc. tag	Set 1¼"x20" Rod & cedar post w/loc. tag
6" Maple N23°E 14.9	9" Maple N38°W 23.0
4" Maple S48°E 21.1	6" Maple N27°E 16.5
6" Maple S05°W 25.9	16" Maple S88°E 16.5
6" Maple N83°W 15.5	10" Maple S11°E 48.1

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 10 Established 1/16 corner S.P.
- 11 Established center of SW¼ of Sec. 25 per std. B.L.M. instructions.
- 13 Established center SE¼ of Sec. 25 per std. B.L.M. instructions.
- 14 Set 1/16 corner S.P.
- 16 Established 1/16 corner S.P.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10	11	13
Drove 1¼"x2' iron rod & set cedar post w/loc. tag	Set 1"x36" Pipe & cedar post w/loc. tag	Set ½"x48" iron bar & cedar post w/loc. tag
10" Cherry S12°E 91.4	6" Maple N25°W 55.0	4" W. Pine N10°E 41.1
8" Cherry S81°E 131.0	5" Maple N33°E 52.8	7" Cedar N32°E 97.7
8" Maple N75°W 70.1	5" B.Cherry N56°W 94.6	8" Maple S05°W 73.0
Ctr. N-S sand rd. Due W 27'±	Fd. pipe & cedar post N78°56'30"E 63.48	9" W. Birch S77°W 23.1

SIGNED BY Carl F. Roser DATE 10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

RAPID RIVER TOWNSHIP  
KALKASKA COUNTY