

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 28 ^{N.} R. 7 ^{W.}	L-7; M-7
2. PROPERTY CONTROLLING IN SECTION 13 _____	T. 28 ^{N.} R. 7 ^{W.}	16
3. MISCELLANEOUS PROPERTY IN SECTION 13 _____	T. 28 ^{N.} R. 7 ^{W.} M-5 & 653.60 W. of M-5)	ZZZ (between L-5 & M-5)
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 13, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on December 1, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

ZZZ

Drove 1 1/4"x18" Iron Rod
 12" Maple S27°E 44.55
 24" Maple S69°W 77.45
 Ctr. E-W b'top road
 Due N 1'±
 Set cedar post w/loc. tag
 Due S 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 Accepted 1" pinch pipe as set by C.P.C. in 1967 which fits surveys of W 1/2 of Sec. 13 by W. S. Merrill in 1910 and B. L. Caukin in 1919.
- M-7 Drove 1 1/4"x54" pipe in pond & crimped 1" pipe with DNR cap in 1 1/4" pipe. Set from RLS Corey Hughes witnesses which fits his survey to N-S-E.
- 16 Reestablished 1/16 corner equidistant between C.P.C. 1/4 corner to W & C.J.H. section corner to E.
- ZZZ Established NE corner of W 1/2-NE 1/4-NE 1/4 per standard subdivision of NE 1/4 of Section 13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7	M-7	16
Fd. 1" pipe & added DNR mon. & cedar post	Set DNR mon. & cedar post	Drove 5/8"x36" rerod w/plastic cap & set cedar post w/loc. tag
10" Maple S67°E 49.2	20" Basswood N51°E 10.32	11" Cherry N35°W 30.9
7" Twn. Maple S45°W 19.4	7" Twn. Basswood S41°E 4.71	14" Maple S25°W 28.1
8" Maple N46°W 52.6	11" Maple S25°W 19.82	10" Cherry S50°E 42.5
8" Twn. Maple N38°E 54.4	Fd. 1/2" pipe Cap #20706	Fd. 1" pinch pipe S81°25'W 21.74
	S00°30'W 12.42	

SIGNED BY Carl F. Roser 10-31-77 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

RAPID RIVER TOWNSHIP
KALKASKA COUNTY