

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> ^{N.} <u>7</u> ^{W.}	<u>K-7; K-8</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u>	, T. <u>28</u> ^{N.} <u>7</u> ^{W.}	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION <u>23</u>	, T. <u>28</u> ^{N.} <u>7</u> ^{W.} S00°34'W, 663.24 from K-8)	<u>X (between K-8 & K-9</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 10, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on May 13, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and for subsequent restoration:~~

C. (continued)

X

Drove 1 1/4" x 16" Rod		
9" Cherry	S61°E	50.43
18" Cherry Twn.	S38°W	57.44
32" Maple	N45°W	43.26
Set cedar post w/loc. tag	Due W 33'	
Ctr. N-S sand trail	Due W 6'±	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-7 Accepted 2" pipe as recovered by C.P.C. in 1967.
- K-8 Found 1" pipe; by C.P.C. in 1967; and raised with 1/2" rod.
- 7 Found 1/2" x 3" iron as recovered by C.P.C. in 1967 & set 5/8" x 36" rerod.
- X Established NE corner of S 1/2 - NE 1/4 - SE 1/4 of Sec. 23 per std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7	K-8	7
Fd. 2" pipe & set cedar post w/loc. tag	Fd. 1" pipe ^{Drove} & 1/2" rerod over top	Set 5/8" x 36" rerod & cedar post w/loc. tag
8" Maple N42°E 32.1	10" B.Cherry (clstr.) S62°E 63.1	9" Ironwood S27°W 45.8
9" Maple N52°W 19.4	10" Maple (clstr.) S17°W 100.5	9" Maple N58°W 69.4
20" Y. Birch S65°W 76.2	8" B.Cherry (clstr.) N65°E 37.1	5" Ironwood N28°E 32.9
6" Maple Clstr. S68°E 26.3		9" Maple S80°E 37.1

SIGNED BY Carl F. Roser

DATE 10-31-77

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

RAPID RIVER TOWNSHIP
KALKASKA COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____