

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Kalkaska _____
 (County)

- | | | | | | |
|--------------------------------------|---------|---------|---------|-----------|--|
| 1. Public Land Survey | T _____ | R _____ | | | |
| | T _____ | R _____ | | | |
| 2. Property Controlling in Section | S 13 | T 28N | R 7W | CENE 1/64 | |
| | S _____ | T _____ | R _____ | | |
| 3. Miscellaneous Property in Section | S _____ | T _____ | R _____ | | |
| | S _____ | T _____ | R _____ | | |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept. 16, 2004 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
CENE 1/64 - None

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

CENE 1/64 – being the NW Cor. of the E 1/2 of the SE 1/4 of the NE 1/4 of Sec. 13 - No corner evidence found. Set 2" Aluminum Cap, stamped on 5/8" x 34" rebar per standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
CENE 1/64 – 2" Aluminum Cap on 5/8" x 34" rebar

- N35°W 25.22' to set N & T in W side 10" Sugar Maple
- S47°W 34.73' to set N & T in S Side 3" Ironwood
- S55°E 35.92' to set N & T in NE side 4" Sugar Maple
- N30°E 13.87' to set N & T in E side 16" Sugar Maple Clp. - 4
- Set Blue Carsonite Post 1' SW



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 12/7/2009