

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 28 N. 8 E. S. 1	C-4 C-5
2. PROPERTY CONTROLLING IN SECTION 7	T. 28 N. 8 E. S. 1	6 & 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. E. S. R.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 1-3 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-4 Reestablished corner per standard B.L.M. instructions.
- C-5 Accepted existing concrete monument as tied in plat of "Chaney Park".
- 6 Established corner per standard B.L.M. instructions.
- 7 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

C-4	Code 6	Code 9
Set DNR Conc. Mon w/St fn post	Set DNR Conc. Mon.	Set DNR con. mon w/St fn post
12" R. Pine N79E 56.6'	7" Balsam N83W 30.56'	P.P. S45E 14.35'
12" R. Pine S68E 34.3'	3" Cedar S67W 18.59'	12" W. Pine N15W 43.21'
10" R. Pine S14W 81.6'	5" Balsam S24W 20.75'	24" W. Pine N60W 26.72'
Exist. Conc. Mon N88W 27.4'	Exist. con mon S85W 20.1'	Exist. con mon S72E 25.6'

C-5
Fd. 4" Round Conc. Mon.
5" Ced. S08 E 19.0'
7" Ced. N84E 14.0'
5" Ced N38W 16.0'

SIGNED BY Carl F. Roser DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

