

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


KALKASKA COUNTY
T 28 N R 5 W

DESCRIPTION OF CORNER 1/4 CORNER COMMON TO SECTIONS 7-8

CORNER MONUMENT SET DEPT. MON.

DATE MONUMENT PLACED AND WITNESSED 6-30-69

WITNESSES TO CORNER.....



	<u>7" Oak</u>	<u>S 05 E</u>	<u>49.3'</u>
	<u>6" Oak</u>	<u>N 84 E</u>	<u>66.8'</u>
	<u>W. Pine Stp.</u>	<u>N 79 E</u>	<u>48.1' (B.L.C)</u>
AND	<u>*24" W. Pine Stp.</u>	<u>N 27 E</u>	<u>75.3'</u>
	<u>Old NBT - No record.</u>		

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS FOUND DURING A RETRACEMENT IN THIS TOWNSHIP. FOUND POST BOTTOM AND IRON BAR AT CORNER AS ESTABLISHED BY B. L. CAUKINS IN 1919 SURVEY. MANY CORNERS IN SECTIONS 5, 6, 7, 8 HAD TO BE ESTABLISHED BECAUSE OF FRAUDULENT OR ERRONEOUS GOVERNMENT SURVEY IN THIS AREA, AS INDICATED BY MEANDERS OF STARAVATION LAKE. MOST EARLY DEVELOPMENT OF THIS AREA BELIEVED TO BE REFERENCED TO CAUKINS CORNERS, AND NOTHING MORE DECISIVE IS AVAILABLE. SECTION 7 SUBDIVISION BY CAUKINS BASED ON THIS LOCATION. THE MEANDER CORNER ON NORTH SIDE EAGLE LAKE, BY B.L.C. WAS ALSO RECOVERED, FROM WITNESSES, AT WATER'S EDGE, AND MARKED WITH A 1 1/4" pipe.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED *Kenneth D. O'Leary* DATE 7-25-69
REGISTERED LAND SURVEYOR 10068

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing