

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


KALKASKA COUNTY
T T28 N R 5 W

DESCRIPTION OF CORNER 1/4 CORNER COMMON TO SECTIONS 4-9

CORNER MONUMENT SET DEPT. MON.

DATE MONUMENT PLACED AND WITNESSED 6-30-69

WITNESSES TO CORNER..... 8" Bl Cherry S 65 W 5.3'



40" W Pine Stp S 39 E 115.6'

* Cons. Mon S 14 W 34.54'

AND

* Tuller 1/4 Corner

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS FOUND DURING A SURVEY IN THIS TOWNSHIP. FOUND B. L. CAUKINS POST BOTTOM AT CORNER, FROM HIS RECORD NBTs, AS ESTABLISHED IN 1919 SURVEY. CAUKINS CORNER USED IN 1919 SUBDIVISION OF SEC. 9, AND IS RELATED TO OTHER CONTROLLING CORNERS IN THIS VICINITY. TULLERS CONCRETE MONUMENT ESTABLISHED IN DISREGARD OF USUAL RESTORATION PROCEDURES, AND DOES NOT CONFORM TO LARGE AREA PATTERN OF SURVEY. MANY CONFLICTING CORNERS AND LINES IN SECTION 4.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Kenneth Deuling
REGISTERED LAND SURVEYOR 10068

DATE

7-25-69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing