

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 5 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Meander corner common to Sections 20-29 on E. Side of Papoose Lk.

CORNER MONUMENT Set 1 1/2" pipe and post

DATE MONUMENT PLACED AND WITNESSED 8/8/68

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

* 12" W. Pine stub N 66 E 27.1'

* 36" W. Pine stp S 33 W 21.7'

AND

* Caukins witness

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established during a retracement in this township. Set corner on the calculated section line on east margin of Papoose Lake. This position falls 4.6' South of Caukins M.P., which was intended to be on the section line.

SURVEYOR'S SEAL

SIGNED *Kevin J. Ostling* DATE 9/5/68
REGISTERED LAND SURVEYOR #10068