

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 5 W


Kalkaska COUNTY

DESCRIPTION OF CORNER Meander Corner common to Sec. 20-29 on West Side of Papoose Lake

CORNER MONUMENT Set 2" pipe with "T"

DATE MONUMENT PLACED AND WITNESSED 8/8/68

WITNESSES TO CORNER.....



* 24" W. Pine Stump N 47 W 8.9'

* 24" W. Pine Stump S 14 W 20.8'

AND * B. L. Caukins witness

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored during a survey in this township. Set corner on calculated true section line, at west margin of Papoose Lake.

Caukins M.P. was 2.5' North of true line, but record indicates it was intended to be on straight line with 1/4 and Section corner.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 9/5/68
REGISTERED LAND SURVEYOR #10068