


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

KALKASKA COUNTY
T 28 N R 5 W

DESCRIPTION OF CORNER SECTION CORNER COMMON TO SECTIONS 8-9-16-17
CORNER MONUMENT SET DEPT. MONUMENT
DATE MONUMENT PLACED AND WITNESSED 6-30-69
WITNESSES TO CORNER.....



20" Beech N 20 E 14.1'
6" Maple S 75 W 17.3'
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established during retracement of this township. Set corner by double proportionate measurement between corners one mile each direction. Unable to recover B. L. Caukins corner, which was established by questionable procedure on a three mile straight line without regard for E-W measurements that would result in highly unequitable distribution of lands in Sections 8-9-16 & 17.

Our method of double proportion distributes available lands more in conformity with the intent of the U. S. survey and involves mostly state ownership.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Kenneth Ostling
REGISTERED LAND SURVEYOR 10068

DATE

7/25/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing