

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28. NR. 5. W. . . .

----- Kalkaska ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner on north side of Section 4 on
north boundary of township.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER -----

6" Cherry - S39W - 65½ links

6" Cherry - S46E - 79 links


DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners of Section 4 by Forestry Division survey crew while making a survey of the south half of T29N R5W.

1/4 corner for Section 33, T29N R5W is 14 links east.

Corner was placed and witnessed April 9, 1957.

SURVEYORS SEAL



SIGNED Billy D. Buckles
REGISTERED LAND SURVEYOR

DATE 5/13/57