

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -:	LOCATED IN -:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>5</u> R. <u>W.</u>	L-13; <u>M-10</u> ; M-11; M-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 10-5, 19 77, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A - Description of original monument and accessories and/or subsequent restoration:

C. (continued) M-12  
 Fd. 1" X 48" Pipe set D.N.R.  
 Mon. & ced. Post  
 5" R.Pine S80°W 46.6  
 9" R.Pine N27°W 36.8  
 3" R.Pine S36°E 8.5  
 Approx. Ctr. of N-S Gas line opening  
 Due W 165'+

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L-13 Estab. 1/4 Cor. equidistant & on line Btw. fd. sec. Cors. to E & W. Cor. falls 27'+ South of E-W Power line.  
 M-10 Fd. Dept. Mon. from previous Dept. Survey of 1951 which perpetuated Cor by M. Schaaf (1946) who's notes indicate he had U.S.B.T. sites.  
 M-11 Recovered 1/2" pipe & 3" sq. ced. post which fits 3 fd. M.Schaaf Wits. (1944). Schaaf notes indicate he had U.S.B.T. sites.  
 M-12 Fd. & accpeted 1" X 48" pipe. Schaaf position per his wits. (Physical Corner not fd.) would be N50°12'W, 5.5'.

C. Description of monument for corner and accessories established to perpetuate M-11 locating the position of the corner:  
 L-13 M-10 Fd. 1/2" pipe & replaced w/DNR mon. & ced. post

Set DNR Mon. & ced. post	Fd. Dept. Mon. & ced. post	10" R.Pine S38°W 93.2
P.Pole N51°W 44.64	8" W.Pine S72°E 24.4	7" R.Pine N08°E 120.4
7" Tamarack S74°E 59.3	12" Tamarack S19°W 61.2	9" R.Pine S01°E 82.4
6" Tamarack S55°E 44.9	18" Maple N71°W 43.2	R.Pine N82°W 69.8
8" Cedar S44°W 56.8	Ctn N-S Gas line opening	Approx. Ctr N-S gas line opening
	Due W 200'+	Due W 190+
	10' Stream Due S 210'+10'	
	26" W.Pine S31°E 110.5'	

SIGNED BY Carl F. Roser DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ BLUE LAKE TOWNSHIP  
 KALKASKA COUNTY