

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>28</u> N. <u>5</u> W. <u>5</u>	J-5
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>28</u> N. <u>5</u> W. <u>5</u>	1; 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Corey J. Hughes, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 3, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-5 Set DNR monument midway on line as per B.L.M. instructions.
- 1 Set by standard procedure for the subdivision of sections.
  - 2 Set by standard procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5	1	2
Set DNR mon. & cedar post	Set 3/8"x1/2"x30" iron & Ced. post	Set 1/2" hexagon iron & cedar post W/Loc Tag
4" Maple S36°E 60.2	W/Loc Tag & 3 stones	Basswood Clmp. N40°E 30.5
7" Maple S09°W 49.6	10" Triple Maple S72°W 22.3	7" Basswood S77°E 9.9
6" Twin Maple S48°W 38.0	Maple Clmp. (3) S06°E 47.3	7" Maple S57°W 23.0
Gas Pipe line 850' East	Maple Clmp. (5) S58°E 46.9	EW R/L 8.28' South
EW R/L 5.5' South	N-S two-track 77' West	NS Road 235' East

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:


Above corners by Corey J. Hughes, R.L.S. #20706; Title X Survey for Mich. D. \_\_\_\_\_ 1976

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Carl F. Roser 1-16-78 DATE \_\_\_\_\_

Carl F. Roser

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

BLUE LAKE TOWNSHIP  
KALKASKA COUNTY