

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>20</u>	T. <u>28</u> N. S., R. <u>5</u> E. W.	<u>10; 2</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 13, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 10 - DROVE 5/8" X 36" REROD FOR NW COR OF SW-SW OF SEC 20. CORNER FITS PROBABLE B.L. CAUKINS B.T. REMAINS (ROTTED HEMLOCK MOUNDS). CORNER SET MID-WAY AND ON LINE BETWEEN 1/4 COR NORTH AND SEC CORNER SOUTH.
- 2 - DROVE 5/8" X 36" REROD FOR NW CORNER OF NE-NE OF SEC 20, MID-WAY AND ON LINE BETWEEN FD. NE & N 1/4 COR OF SEC 20. A DEFINITE POST BOTTOM HOLE IS 1.3' WEST (PROBABLY B.L. CAUKINS).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>10</u>	<u>2</u>
DROVE 5/8" X 36" REROD W/RLS CAP & SET CEDAR POST W/LOC TAG.	DROVE 5/8" X 36" REROD W/RLS CAP & SET CEDAR POST W/LOC TAG.
10" MAPLE N65°E 17.6	5" MAPLE N85°E 9.6
5" W. BIRCH S70°E 43.0	5" MAPLE N26°W 22.5
2" MAPLE S60°W 28.1	6" MAPLE S50°W 24.4
N-S RANDOM WEST 4.7	OLD E-W RANDOM SOUTH 30'±

SIGNED BY Carl F. Roser 5-02-83 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BLUE LAKE TWP.  
KALKASKA COUNTY